No.	Items of work	Unit	Cost	Quantity
			Rs. a. p.	
6	Burnt stone slabs 4″ to 6″ thick dressed and fixed in cement mortar (1 : 6)	S.ft.	0 14 0	21
7	Drilling holes in slabs	Each	1 0 0	4
8	Providing and fixing C. I. pipe 5″ diar. 12 feet long including the cost of railway freight, cart hire to spot, fixing and jointing, etc., complete	R.ft.	3 0 0	36
9	Cement pointing to Masonry	Sqr.	4 0 0	1·00
10	Do plastering	,,	6 0 0	0·50
11	Providing and fixing a teakwood plug and iron rod with locking arrangement	L. S.	..	..
12	Rough stone work new	C.yd.	2 8 0	5
13	Unforeseen items	L. S.	..	..

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 4th April 1940.

The attention of the public is invited to the Notification published on pages 831-834 of Part VI of the *Mysore Gazette* dated 11th April 1940 calling for tenders for the work of constructing "a new pair of masonry settling tanks for Chikmagalur Town Water-supply" at Chikmagalur. The last date of the receipt of tender in this office is 25th April 1940.

C. NARAYANASWAMI SETTI,
For *Executive Engineer*.

ANJANAPUR DIVISION.

Notification dated 11th April 1940.

1. Sealed tenders will be received at the office of the Executive Engineer, Anjanapur Division, up to 3 P.M. on 10th May 1940, for Restoring Muthige Jagalikatte, Major Tank Register No. 834, Shikarpur Taluk.

2. Tenders in the prescribed form obtainable on payment of Re. 0-4-0 per form from the office of the Executive Engineer, Anjanapur Division, should be addressed to the Executive Engineer, Anjanapur Division in a sealed cover and be superscribed as "Tender for Restoring Muthige Jagalikatte, Major Tank Register No. 834, Shikarpur Taluk". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 680 under "17 (*a*) P.W. Deposits" or Mysore Government Bonds duly endorsed at face value or market value whichever is less as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th May 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Anjanapur on all working days between 8 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender, and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections, made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm it must be signed separately and severally by each member thereof or in the event of absence of any partner it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent an may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940; failing which the Executive Engineer may at his discretion levy a penalty of Rs. 1-4-0 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc.; the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers, will, however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgements of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns water pumps and hoses, sleves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baing of water from excavations and foundation wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the Public Works Department so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for restoring Muthagi Jagalikatte, Major Tank Register No. 834, Shikarpur Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be quoted in	
					Figures	Words
	Bund R.L. 56·00, *Top width* 6 *feet, Slopes* 2 : 1.		Rs. a. p.		Rs.	Rs.
1	Clearing jungle with roots	Grade	2 0 0	48		
2	Cutting grips and stops..	,,	2 0 0	48		

No.	Items of work	Unit	Rate	Quantity	Rates to be quoted in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
3	Earthwork to bund with watering and consolidation including a lead of 660 feet and a lift of 20 feet	C.yd.	0 5 0	25,190		
4	Turfing to front and rear slopes of bund ..	S.yd.	0 0 9	23,215		
5	Providing and fixing grade stones in cement concrete including cutting figures and painting	Each	2 0 0	48		
6	Providing and fixing Index stones do ..	,,	1 0 0	48		
7	Do B.M. stones do ..	,,	5 0 0	2		
8	Do Reg. No. and date stones do ..	,,	5 0 0	1		
	II. Left Waste Weir 60 ft. long at R.L. 51·00.					
1	Earthwork excavating foundation ..	C.yd.	0 3 6	108		
2	Stone jelly concrete in cement mortar 1 : 6 : 12	C.ft.	0 6 6	602		
3	Size stone in cement mortar 1 : 6 ..	,,	0 6 0	909		
4	Cement concrete coping 1 : 2 : 4	,,	1 0 0	72		
	(*a*) Do do 1 : 4 : 8 ..		rate may	be quoted		
5	Cement pointing 1 : 4	Sqr.	4 0 0	8·75		
6	Rough stone work, new	C.yd.	2 8 0	67		
7	Draft and approach clearing	L.S.	25 0 0	..		
	III. Right Waste Weir 100 ft. long at R.L. 51·00.					
1	Earthwork excavating foundation ..	C.yd.	0 3 6	166		
2	Stone jelly concrete in cement mortar 1 : 6 : 12	C.ft.	0 6 6	912		
3	Size stone in cement mortar 1 : 6 ..	,,	0 6 0	1,278		
4	Cement pointing 1 : 4	Sqr.	4 0 0	12·35		
5	New rough stone work	C.yd.	2 8 0	93		
6	Cement concrete coping 1 : 2 : 4	C.ft.	1 0 0	113		
	(*a*) Do do 1 : 4 : 8 ..		rate may	be quoted		
7	Draft and approach clearing ..	L.S.	119 0 0	..		
	IV. Constructing 3 C.I. Pipe Sluices at R.L. 44·00, 36 ft. long 6 inches diameter (Details for each).					
1	Earthwork cut opening bund and refilling with watering and consolidation ..	C.yd.	0 6 0	53		
2	Earthwork excavating foundation ..	,,	0 3 6	6		
3	Stone jelly concrete in cement mortar 1 : 6 : 12	C.ft.	0 6 6	167		
4	Size stone in cement mortar 1 : 6 ..	,,	0 6 0	269		
5	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	1 0 0	51		
6	Cement plastering 1 : 4 ; ½″ thick ..	L.S.	8 0 0	..		
7	Providing and fixing 6″ dia. C.I. pipes including carting, fixing and jointing ..	R.ft.	2 4 0	36		
8	Cement pointing	L.S.	4 0 0	..		
9	Cutting holes in slabs	Nos.	1 0 0	4		
10	Providing and fixing T.W. plug and rod with locking arrangements, etc., complete	,,	12 0 0	1		
11	New rough stone revetment in front and rear of sluice	C.yd.	2 8 0	25		
	V. Constructing two C.I. Pipe Sluices at R.L. 47·00. (Details for each).					
1	Earthwork cut opening bund and refilling with watering and consolidation ..	C.yd.	0 6 0	36		
2	Earthwork excavating foundation ..	,,	0 3 6	4		
3	Stone jelly concrete in cement mortar 1 : 6 : 12	C.ft.	0 6 6	109		

No.	Items of work	Unit	Rate	Quantity	Rates to be quoted in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
4	Size stone in cement mortar 1 : 6	C.ft.	0 6 0	128		
5	Cement plastering 1 : 4 ; ½" thick	L.S.	8 0 0			
6	Providing and fixing 6" dia. C.I. pipes including carting, fixing and jointing	R.ft.	2 4 0	33		
7	Burnt stone slabs 6" thick dressed and fixed	S.ft.	1 0 0	42		
8	Cutting holes in slabs	Nos.	1 0 0	3		
9	Providing and fixing T.W. plug and rod with locking arrangements, etc., complete	„	12 0 0	1		
10	Cement pointing 1 : 4	Sqr.	4 0 0	1·00		
11	New rough stone revetment in front and rear of sluice	C.yd.	2 8 0	25		

N. G. KRISHNA IYENGAR,
Executive Engineeer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, dated 19th November 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE AGRICULTURAL ENGINEER, HEBBAL FARM, BANGALORE.

Notification No. 13, *dated* 30*th March* 1940.

An old Fordson Tractor 12-20 H.P. with all parts complete will be sold by public auction by the Agricultural Engineer on the Hebbal Farm on 20th April 1940.

The sale conducting officer may, at his discretion, refuse to accept the bid of any person without assigning any reason.

The person in whose favour the article is knocked down, shall pay the full amount immediately and make his own arrangement to its removal. In case the person whose bid is accepted fails to pay the full amount, the article will be resold immediately at the risk of the original purchaser.

M. G. SINGARACHAR,
Agricultural Engineer.

OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, BANGALORE CIRCLE, SESHADRI ROAD, BANGALORE.

Notification No. I—39-40, *dated 9th April* 1940.

In inviting attention to notification, dated 1st March 1940, regarding the auction sale of Mango Crop belonging to Ramakrishna Krishi Shala, the public are hereby informed that the auction sale is postponed to 3rd May 1940, and intending bidders may bid for the same at the auction, which will be held in front of the Agricultural Sub-depot, Anekal, at 2 P.M.

B. DASAPPA,
Assistant Director.